

**BILL OF QUANTITIES OF ELECTRICAL WORKS AT 14 NOS. OT**

S.No.	Description.	Qty.	Unit.	Rate in Figures (in Rs.)	Amount in Figures ( in Rs.)
1	2	3	4	5	7
1.00	Installation, testing and commissioning of following light fixtures with lamps, low loss vacuum pressure impregnated open construction copper ballast (5.5 watt loss) push fit bi-pin rotor lamp holder, push fit starter holder, starter, capacitor, connecting terminal etc. complete with all fixing accessories etc. inclusive of internal wiring. Heat resistant, sleeving and making connectors including flexible conduit etc.				
	a) 2X 36 watt wide spread mirror optic recess mounting type fluorescent light fixture in white finish with pre anodized high purity parabolic mirror aluminium reflector (M1), aluminium cross louvers complete with all accessories of cat Ref: Philips TBS 285/236 HPF	140	Each		
	b) 2X 9 watt recessed mounting CFL down lighter in white finished with pre anodized aluminium reflector, prismatic acrylic diffuser complete with all accessories as required of CAT Ref: Crompton Greaves DDLH 29A or approved equivalent	196	Each		
2.00	Installation, testing commissioning of ionisation type Smoke Detectors with LED mounting base including connection complete as required	70	Each		
3.00	Internal wiring with multiple 2X 4 Sq. mm copper conductor 2nd 2.5 Sq. mm core in MS conduit including supply (in all 14 nos. OT)	100	Metre		
4.00	Supply, fixing of modular type switch 6 pin socket, cover plate etc as required (in all 14 nos. OT) including modular box.	60	Each		
<b>TOTAL</b>					