

HSCC/PG-I/103J/03/2010

Dated 13-04-2010

Corrigendum-II

Subject : Tender for the work of Construction of Staff Quarter, temporary kitchen & renovation of Kitchen, Laundry & Nurses hostel at LRSI TB hospital, Mehrauli, New Delhi – Minutes of Prebid meeting

Sir,

A pre bid meeting was held in HSCC corporate office, Noida on 31-03-2010 at 15.00 hr. as mentioned in Notice Inviting Tender. The points raised by the prospective bidders and amendments issued are as follows:

1) To expedite progress of work, item of ready mix concrete should be included:

Item of Ready Mix Concrete has been included in the Bill Off Quantities (BOQ) and is given in annexure I.

2) If the bidder is permitted to dispose off the unserviceable and serviceable material and adjust the cost of the same in the quoted rates, this will reduce the cost of dismantling:

BOQ item no. 19.01 has been amended and is given in annexure I.

. Note

- 3) BOQ Item no. 3.08 stands deleted.
- 4) Quantity of BOQ item no. 3.02 may be read as 601 Cu. M instead of 1201 Cu. m.
Annexure I shall remain the part of price bid.

The clarifications given above shall be the part of contract document and is to be submitted along with the tender document duly signed & stamped. Other terms and conditions of the tender and schedule shall remain unchanged.

Encl. – Annexure I (02 Pages)

Thanking You
Yours faithfully

(R.S. Raina)
General Manager (PG-I)

| | Bill Of Quantities (Amendment as per minutes of Prebid meeting) | | | | Annexure-I |
|----------------|---|-------------|-------------|---------------------------|---------------------|
| | PROJECT: Tender for the work of Construction of Staff Quarter, temporary kitchen & renovation of Kitchen, Laundry & Nurses hostel at LRSI TB hospital, Mehrauli, New Delhi | | | | |
| | | | | | |
| Item No | Description Of Item | Unit | Qty. | Rate in Words (Rs) | Amount in Rs |
| 3.00 | RCC | | | | |
| 3.09 | “ Providing and laying in position ready mix concrete manufactured in fully automatic batching plant and transported to site of work in transit mixer having continuous agitated mixer , manufactured as per mix design of specified grade for reinforced cement concrete work including pumping of RMC from transit mixer to site of laying , excluding the cost of centering , shuttering finishing and reinforcement including cost of admixtures in recommended proportions as per IS:9103 to accelerate/retard setting of concrete, improve workability without impairing strength and durability as per direction of the Engineer –in-charge. M-25 grade reinforced cement concrete by using 410 kg of cement per cu. of concrete. All work up to floor V level. (Rates are inclusive of all leads) Approved RMC plant are Birla, ACC, L&T & Ahlcon . | | | | |
| a) | RCC M-25 grade | Cum | 600 | | |
| | | | | | |

| Item No | Description Of Item | Unit | Qty. | Rate in Words (Rs) | Amount in Rs |
|---------------|--|------|------|--------------------|--------------|
| 19.01 | <p>BOQ item No. 19.01 has been replaced with the following item:</p> <p>Dismantling of existing buildings/toilet and other structures comprising of concrete , RCC, brick work, flooring, finishes ,pavement, external services etc. including taking out all doors, windows and ventilators, roofing, electrical, water supply sanitary installation, rain water pipe with all fittings and fixtures etc . complete. The job also include all excavations, fillings, leveling etc. and including the cost of transportation and disposal of all the unserviceable materials to the nearest municipal dumping ground complete . The entire site of dismantled buildings/ structures shall be cleared and levelled as directed.</p> <p>The dismantled material except electrical fittings and fixtures shall be the property of contractor and shall be assumed as bought by the Contractor. Contractor has to quote the rates accordingly.(Bidders may actually verify the details from site.)</p> <p>Approx covered area of building to be dismantled are as follows:</p> | | | | |
| | (a)Existing abandoned old staff quarter for temp. kitchen (Area at GF =275 Sq. m & at FF =160 Sq. m) | | | | |
| | b) Existing Kitchen G.F = 411 Sq. m | | | | |
| | c) Existing abandoned old staff quarter for Laundry (Area at G.F =200 Sq. m) | | | | |
| | d) Existing old toilet block for Nurses hostel (Area at GF =50 Sq. m & at FF =50 Sq. m) | | | | |
| (i) | Cost of dismantling and disposal for the above work.- | Sqm | 1146 | | |
| (ii) | Credit for the servicable material such as door, window, ventilator shutters & frame, brick, steel etc.and other scrap material obtained by the contractor from the dismantling of above structure- | Sqm | 1146 | | |
| Note : | | | | | |
| 1 | BOQ item No. 3.08 stands deleted | | | | |
| 2 | Quantity of BOQ item no. 3.02 may be read as 601 cum. Instead of 1201 cum. | | | | |