

ADDENDUM / CLARIFICATIONS

Subject: Tender for establishment of STP and piping for ICMR Pune

Reference: IFB Ref.: HSCC/MCC/PG-III/STP/2010

This is with reference the letter received from a prospective bidder, the point-wise clarification are as under:

S.No.	Issue	Clarification for the agency
1	Bioreactor- 4 nos., Tube Settler- nos. and sludge pump- 2nos. have been proposed on pg no. 6 in part-A, units of equivalent capacity to mmske the system economical. Please clarify.	No. of units proposed in tender shall remain unchanged.
2	Screen- 2 nos. Submersible pump- 4 nos., Blower-6 nos. and Filter Press-2 nos. have been proposed on pg.no.7 in part-A, Vol. IV of the tender. It is possible to make less no. of units of equivalent capacity to make the system economical. Please clarify.	No. of units proposed in tender shall remain unchanged.
3	Rotary Air Blower has been mentioned on pg. no. 3 on part-B. Other places twin lobe blower has been mentioned. We understand that twin blower will be used for this purpose.	Rotary Air Blower shall be read as Twin Lobe Roots Blower (Rotary).
4	For excess sludge treatment Centrifuge has been mentioned in part-A, Vol.IV of the tender. However, in drawing and price bid, filter press is mentioned. Please clarify.	Only Filter Press and Sludge Drying Beds as per the specification shall be provided for excess sludge treatment. Centrifuge shall be considered deleted from the tender document.
5	The price of the pre-treatment unit (Ref. pg. 11 of price bid) shall be quoted on per cum basis or per 10cum/20cum basis.Please clarify.	The price of pre-treatment unit shall be quoted as per cum. Basis.
6	Scope of work of shed and Equipment Room should be elaborated.	<ul style="list-style-type: none">• RCC / Brick covered room will be required for, Electrical panel, Lab Equipment, Non submersible pump, Filter press, Dosing pump etc. of minimum size 36sq.m. or as per the size required for these items.• The shed will be required for protection of Blower/ Pumps/ Filter press from weather as per site condition. The shed will have roofing of Pre-coated Galvanized Iron profile sheet as per DSR item 12.50 with standard steel frame & PCC base.
7	DPCB	Wherever DPCB is mentioned in the Bid Document the same should be read as MPCB.