

Dated: 25.07.2025

AMENDMENT No.- I

Project Name: Tender for “Construction of Boundary wall at left out areas & other miscellaneous works including their Maintenance during Defect Liability Period at National cancer Institute, Jhajjar, Haryana”

Tender No. HSCC/AIIMS/NCI-JHAJJAR/BW/2025/120, dated 18/07/2025

This has reference to subject work, the following Amendment may be noted, which shall be treated as a part of the contract to be uploaded along with tender/ bid:

1. Refer Vol.-V (Bill of Quantities) of tender documents, the following items “Unit” are hereby amended/revised as follows:

Sr. No.	DSR No.	Description of Items	Unit as per BOQ items	Revised Unit
6.01	13.72	Washed stone grit plaster on exterior walls height upto 10 metre above ground level, in two layers, under layer 12 mm cement plaster 1:4 (1 cement : 4 coarse sand), furrowing the under layer with scratching tool, applying cement slurry on the under layer @ 2 Kg of cement per square metre, top layer 15 mm cement plaster 1:1/2:2 (1 cement: 1/2 coarse sand : 2 stone chipping 10 mm nominal size), in panels with groove all around as per approved pattern, including scrubbing and washing the top layer with brushes and water to expose the stone chippings ,complete as per specification and direction of Engineer-in-charge (payment for providing grooves shall be made separately).	Kg	Sqm
6.02	13.73	Forming groove of uniform size in the top layer of washed stone grit plaster as per approved pattern using wooden battens, nailed to the under layer, including removal of wooden battens, repair to the edges of panels and finishing the groove complete as per specifications and direction of the Engineer-in-charge :		
a)	13.73.1	15 mm wide and 15 mm deep groove	Sqm	mtr
7.03	15.3	Demolishing R.C.C. work manually/ by mechanical means including stacking of steel bars and disposal of unserviceable material within 50 metres lead as per direction of Engineer - in- charge.	mtr	Cum
7.04	15.7	Demolishing brick work manually/ by mechanical means including stacking of serviceable material and disposal of unserviceable material within 50 metres lead as per direction of Engineer-in-charge.		
	15.7.4	In cement mortar	mtr	Cum

This amendment becomes integral part of the tender/contract. Bidders are advised to submit their bid accordingly.

Prospective bidders are advised to regularly visit through HSCC e-tender portal **<https://hsccltd.co.in>** & HSCC website <http://www.hsccltd.co.in> as corrigendum/amendments etc. if any, will be notified on this portal only and no separate advertisement will be made for this.

All other terms & conditions of the Tender shall remain unchanged.

(– sd –)
ZIC/ DGM (Engg.)
HSCC (India) Ltd.