



NOTES

1. ALL DIMENSIONS ARE IN mm & LVS IN m.
2. READ IN CONJUNCTION WITH RELEVANT ARCH. DRS
3. FINISHED FLOOR LVL TO BE CONTAINED AS ARCH. DRS, THE SLAB TOP LEVEL TO BE PROVIDED WITH SLOPER, CONSIDERING FLOOR FINISH THICKNESS.
4. CLEAR COVER OF R/F TO BE AS BELOW:-

FOUNDATION	= 50mm
COLUMN	= 40mm
BEAM	= 30mm
SLAB	= 25mm
5. CONC. MIX. TO BE M-25 FOR ALL RCC WORK AS PER IS-456-2000
6. ALL R/F BMS TO BE F-650 Wpa. HYSD OR TMT STEEL AS PER IS-1786.
7. ALL PLP LENGTHS = 500MM/STANDARD BARS AS PER TO PLANNED SUITABLE AS PER SITE REQUIREMENT.
8. DEVELOPMENT LENGTH = 50dBAR ϕ .
9. SEC ASSUMED 100 N/mm² AT 2.0 METER BELOW N.G.L.

0	14.03.13	FOR TENDER
REV	DATE	DESCRIPTION

REVISION

PROJECT

PROPOSED
100 BEDDED HOSPITAL
AT JAUNPUR

TITLE

FOUNDATION LAYOUT PLAN &
COLUMN LAYOUT PLAN

HSCC/ JAUN / D&E / ST-T-101

Drawing No. REV. 02

HSCC/	1:125	MARCH.-201
JOB NO.	SCALE	DATE

APPROVED	REVIEWED	PREPARED
----------	----------	----------

HSCC INDIA LTD.
(A GOVERNMENT OF INDIA ENTERPRISE)